




SKU = [SERIES] [WIDTH] [HINGE DIRECTION] - [LEFT END TYPE] [RIGHT END TYPE]



EXAMPLES U = Unfinished | W = Wall Filler A = Applied Slab Finished End | D = Applied Door Finished End







Standard Features

- ³⁄₄" White Melamine Box Parts
- European Style free swing hinges
- 5/8" White Melamine Drawer Boxes
- Side Mount white epoxy coated drawer guides
- Slab Drawer Fronts
- Applied Finished End Panels
- Flush with Face of Doors
- + Additional $\frac{1}{2}$ " Depth for Scribe to Back Wall
- Standard Applied End Panel stop at Toe Kick (i.e. 4" above Finished Floor)
- Optional Full Height Applied Ends with Toe Notch

PAGE 1 of 4

$\label{eq:barcable} \begin{array}{c} \mathsf{B} \ \mathsf{A} \ \mathsf{R} \ \mathsf{C} \ \mathsf{A} \ \mathsf{B} \ . \ \mathsf{C} \ \mathsf{O} \ \mathsf{M} \\ \mathsf{info@barcab.com} \end{array}$

2020 E. Grant Line Road Tracy, CA 95304 (209) 836-2501 office (209) 836-0847 fax





Note: Variation in color and grain may differ from actual produ




Standard Dimensions

- Heights = 34 1/2" (35 1/4" including Skids)
- Vanities = 32" (32 ³/₄" including Skids)
- Widths = 7 1/2" to 43 1/2" (1 1/2" increments)
- Widths are determined by Cabinet Series
- Depth = 24"
- Vanities = 21"
- Talls = 25 1/2"
- Toe Kick Height = 4" (not including Skid)
- Toe Kick Recess = 2 ³/₄" (not including ¹/₄" Toe Skin)
- Top Drawer Front Height = 6"
- Door Height = 24 1/8" (Full Height Doors = 30 1/4")
- Applied Finished Ends are NOT included in overall Cabinet Width.







PAGE 2 of 4

BARCAB.COM info@barcab.com

2020 E. Grant Line Road Tracy, CA 95304 (209) 836-2501 office (209) 836-0847 fax




Note: Variation in color and grain may differ from actual product.




Standard Reveals

- Left & Right Side Reveals = $\frac{3}{32}$ "
- Top Reveal = 1/4"
- Bottom Reveal = 0"
- Vertical Reveal = 1/8"
- Horizontal Reveal = 1/8"



Standard Construction Details

- 1. ³⁄₄" Melamine Case Parts
- 2.1mm Standard Edgebanding
- 3. Captured 1/4" Back
- 4. Screw & Dowel Construction
- 5.5 Hole cluster for each adjustable shelf (32mm spacing)
- 6. Hinge Boring distance from Top & Bottom of Door = $3 \frac{1}{2}$ "
- 7. Drawer Box Standards
- Heights = 3 1/2", 5", 7", 9 1/4"
- Depths = 9", 12", 15", 18", 21"



PAGE 3 of 4

BARCAB.COM info@barcab.com

2020 E. Grant Line Road Tracy, CA 95304 (209) 836-2501 office (209) 836-0847 fax



Note: Variation in color and grain may differ from actual product





Standard Accessories

- 1. APNL Standard Applied End
 - a. Cabinet Height minus Toe Kick Height
 - b. Flush with Face of Doors/Drawer Front
 - c. Edgebanded on 4 sides
 - d. Additional $^{1\!\!/}_{2}$ " of width for Panel to be scribed to back wall.


2. **APNLTN** – Notched Applied End


- a. Cabinet Height plus $\frac{1}{2}$ " (additional height added for Scribe to Floor)
- b. Panel is notched for Toe Kick flush with face of Front Toe.
- c. Edgebanded on Front & Back Edges
- 3. AROLL Roll Outs
 - a. All Roll-Outs are currently Dovetail Construction and 15mm Baltic Birch Material.
 - b. Height = 4" (will switch to 3 $\frac{1}{2}$ " as Baltic Birch material is replaced)
 - c. Depths = 21", 18", 15", 12"
 - d. Roll-Out quantity = Adjustable Shelf quantity + 1
 - e. Guides match Cabinet Selection
 - f. 26mm Spacer Blocks used on Hinge side for spacing














PAGE 4 of 4

BARCAB.COM info@barcab.com

2020 E. Grant Line Road Tracy, CA 95304 (209) 836-2501 office (209) 836-0847 fax



Note: Variation in color and grain may differ from actual product.

KITCHEN CABINE UFACTURERS ASSOCIATION